



NOTES:

- SPEED LIMIT ON YARROW CENTRAL ROAD IS 50KM PER HOUR
- ALL SIGNS WILL BE PLACED ON TRIPOD STANDS
- SPEED LIMIT ON ALL SIDE STREETS IS 50KM PER HOUR
- ALL SIGNS WILL BE PLACED ON TRIPOD STANDS
- ALL SIDEWALKS WILL REMAIN OPEN
- ALL CROSSWALKS WILL REMAIN OPEN
- ALL BUS STOPS WILL REMAIN OPEN
- FORTIS WILL CONTACT CMBC 3 BUSINESS DAYS PRIOR TO CONSTRUCTION
- TRAFFIC CONTROL WILL ASSIST WITH DRIVEWAYS AFFECTED BY WORK ZONE CLOSURE
- LANE WIDTH WILL BE MAINTAINED AT 3.5 METERS
- ROAD WILL BE RESTORED TO ITS ORIGINAL CONDITION DAILY
- TRAFFIC CONTROL TO COMPLY WITH SECTION 18 OF WORK SAFE BC REGULATIONS

LEGEND

- TRAFFIC CONTROL PERSON
- TCP ESCAPE ROUTE
- WORK ZONE
- ADVANCE WARNING SIGNS
- BUS STOP
- NORTH ARROW
- TUBULAR MARKERS
- FLASHING ARROW BOARD
- DIRECTION OF TRAFFIC
- PEDESTRIAN PATHWAY

Date: January 2024 Author: Michelle Parks - 604-861-9809 Project: 31363702

DWG#: 000 REV#: 000

Comments:

Fortis BC Gas
 Support 3 - Support3@fortisbc.com

City of Chilliwack
 Address: 42474 Yarrow Central Rd
 Scope of Work: Service Abandonment
 Closure Description: WB Single Lane Alternating
 This plan is based on a 50 km/h roadway speed
 All specifications are based on the MoTI manual 2020 edition

