



**TRAFFIC CONTROL PLAN**

DATE OF LAST REVISION  
2018-07-10



Contractor Name:	TCP #	Location:
Universal Contracting	TCP 1 of 1	Bailey Rd @ Elk View Rd, Chilliwack
Job Description:		Dates:
Tank Installation		
Manual for Work on Roadways	Traffic Control Figure Number	
2015 Interim Edition	7.5: Work on Shoulder	
Contractor Contact:	Phone:	Email:
Jeff Boychuk	604-858-8618	jboychuk.universal@gmail.com
Traffic Plan Contact:	Phone:	Email:
Genny Scott	778-860-7247	genny@streetwisetraffic.ca

**LEGEND**

	TRAFFIC CONTROL PERSONNEL		TRAFFIC BARREL
	SIGN STAND (TRIPOD)		TUBULAR MARKER - TYPE D
	SIGN STAND (WINDMASTER)		TRAFFIC CONTROL VEHICLE
	SIGN FLAGS		FLASHING ARROW BOARD (FAB)
	WORKZONE		EXISTING BUS STOP
			RELOCATED BUS STOP

**GENERAL NOTES**

- All traffic control shall conform to the MOTI Traffic Management Manual for Work on Roadways 2015
- Signs shown are representations only and the MOTI Catalogue of Standard Traffic Signs should be used for detailed sign design
- Dimensions shown are in meters and are the minimums except as otherwise indicated
- All permanent signage that will conflict with this site will be covered or removed while the works are in effect
- Active Work Zones and Hazards shall be delineated to protect workers and the travelling public
- Maximum distance between cones/delineator/barrel should be 10m
- Tubular markers and signs will be double based and well secured during windy conditions
- Distances may be adjusted due to urban block length
- These pages are best printed on a Tabloid (11x17) page size

